



February 3, 2012

Wyman Residence Addendum #1

Excavation notes/clarifications

- 1- Native material will be used to backfill the basement floor as noted in the specifications. 3/4" gravel as shown on detail 1/A12 will not be used.
- 2- Native material will be used for all concrete prep as noted in the specifications. 3/4" gravel as shown in details on sheet A12 will not be used.
- 3- Calculated areas are as follows. Gravel Driveway 2453sf, Concrete Apron 100sf, Concrete Sidewalk 351sf, Concrete Patio 338sf.
- 4- At this time include a "Simple Septic System". The excavator will be responsible for the septic permit and complete septic system.
- 5- The site does not need to be cleared and grubbed of trees. Tree location as shown on the site plan is the only area on the site with trees. No trees will be removed for the driveway or home construction. Care should be taken to minimize damage to the existing trees when the water line is installed.
- 6- See attached pictures for site conditions.
Picture 1 was taken near the Electrical Service location looking south. The pine trees in the background are on another lot. The aspen trees on the right are the existing trees on the property.

Picture 2 was taken from the road near the driveway entrance looking east towards the Electrical Service.

Picture 3 was taken near the water supply looking towards the home.



Picture 1



Picture 2



Picture 3